

## ADDENDUM

### Addendum No. 2

Owner: City of Muskegon Date: June 18, 2019  
Project: 9<sup>th</sup> Street Area Sanitary Sewer Improvements & Getty Street Force Main Replacement  
Owner's Contract No.: N/A Engineer's Project No.: 837930  
Engineer: Fleis & VandenBrink Engineering, Inc.

### NOTICE TO ALL PROSPECTIVE BIDDERS

**NEW BID DUE DATE: \*\*\*2:00 p.m. Friday, June 28, 2019\*\*\***

=====

This Addendum is a part of the Contract Documents and modifies the previously issued Bidding Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may result in rejection of the Bid.

### SPECIFICATION CHANGES

#### ITEM NO. 1:

Attached are the following minutes from the pre-bid meeting that was held on June 13, 2019.

- Meeting Minutes for SRF/DWRF project General Items.
- Meeting Minutes for 9th Street Area Sanitary Sewer Improvements & Getty Street Force Main Replacement.

#### ITEM NO. 2:

Section 00 11 13 – ADVERTISEMENT FOR BIDS

Revise the first paragraph and change the bid due date from 2:00 p.m. local time, Thursday, June 27, 2019 to **2:00 p.m. local time, Friday, June 28, 2019.**

#### ITEM NO. 3

Section: SP 00 41 00 – BID FORM

Delete Bid Form in its entirety and replace with attached revised Bid Form.

- Pay Item No. 81 added to include an allowance for railroad flagger.

#### ITEM NO. 4:

Section 32 13 14 – CONCRETE SIDEWALK AND SIDEWALK RAMPS

Delete paragraph 2.01.B and replace with the below paragraph;

B. Concrete: Grade P1, 6.0 sack, air entrained, MDOT 601.

#### ITEM NO. 5:

Section 32 13 14 – CONCRETE SIDEWALK AND SIDEWALK RAMPS

Delete 2.01.H.1, 3, 4, and 6. and replace with the following;

1. Material: Iron, polymer or FRP, per MDOT 803.
3. Color: Brick Red.
4. Provide minimum 5 foot width.
6. Manufacturer: MDOT Qualified Products List.

## **DRAWING CHANGES**

### ITEM NO. 6:

Drawing Sheet C7 – PLAN & PROFILE – 8<sup>TH</sup> ST / HERITAGE LANDING

Replace drawing C7 with the attached.

- Added existing 12" watermain that feeds the hydrant at Sta. 49+50.

### ITEM NO. 7:

Drawing Sheet D3 – CROSS SECTIONS

Replace drawing D3 with the attached.

- Removed lane ties from concrete pavement section for the alley, Sta. 74+58 to Sta. 76+63.

### **ATTACHMENTS:**

- Meeting Minutes
- Bid Form
- Plan Sheet C7
- Plan Sheet D3

**END OF SECTION**